

EXHIBIT A

SCOPE OF SERVICES

Lift Pump Can Procurement. Lift Pump Can and Pump Installation

Project Overview – Procurement and installation of a like-for-like pump can, concrete kicker, soil backfill, shoring removal, concrete pedestal installation, pump installation, pump bolt up, copper drain line reconnection, and off haul/dispose of stockpiled soil

- Procure like-for-like pump can, hardware, gaskets and, miscellaneous material (disposal of the original pump can is included)
- Install the pump can in the previously excavated area of work utilizing the existing piping points of connection
- Pour a concrete kicker at the base of the pump can
- Backfill; the work area with recycled AB
- Removal of the rental shoring
- Installation of an 4'x4'x1' concrete pedestal
- Installation of the existing pump into the pump can
- Pump bolt up to the existing piping points of connection
- Reconnection of an existing copper drain line
- Off haul and disposal of the old pump can, misc. materials
- All stockpiled soil will either be relocated on site or off hauled to an approved disposal facility

General Provisions and Clarifications:

- All work is to be performed during normal working hours on a continuous working schedule coordinated with the customer.
- Any repairs or modifications to the lift pump itself are excluded from this scope.
- Electrical and pump startup are excluded and the responsibility of the customer.
- Restoration of landscaping or surface areas disturbed during excavation is excluded unless explicitly stated otherwise.
- Any unforeseen site conditions requiring additional work beyond the scope outlined are excluded and may incur additional costs.
- Abatement, if found, is not included in the above scope of work.
- Any items not specifically listed above are excluded.
- ACCO will not be responsible for any pre-existing conditions which are not currently in compliance with local mechanical and electrical codes.
- It is assumed that there is no permitting required for this effort.